

**Lampiran 7. Tabel Rencana Anggaran Biaya ( RAB ) Hasil *Redesain***

NO	URAIAN PEKERJAAN	VOLUME	SATUAN	KODE ANALISA	HARGA SATUAN ( Rp )	JUMLAH HARGA ( Rp )
1	2	3	4	5	6	7
<b>A.</b>	<b><u>PEK. PERSIAPAN</u></b>					
1	Papan Nama Proyek	1	Buah	Ls	193,000.00	193,000.00
2	Barak Kerja ( Sewa )	2	Bulan	Ls	200,000.00	400,000.00
<b><i>SUB TOTAL A</i></b>						<b>593,000.00</b>
<b>B.</b>	<b><u>PEK. BANGUNAN SALURAN</u></b>					
1	Pas. Profil Melintang Galian Tanah Saluran	550	m	Analisa T.02.b1)	828.52	455,686.00
2	Galian Tanah Biasa Sedalam $1m \leq x \leq 2m$	893.75	m3	Analisa T.06.a2)	40,837.50	36,498,515.63
3	Timbunan Tanah Atau Urugan Tanah Kembali	316.25	m3	Analisa T.14.a1	19,965.00	6,313,931.25
4	Bekisting	829.341	m2	Analisa B.21.b	76,021.00	63,047,332.16
5	Perancah Bekisting	92.149	m2	Analisa B.21.d	121,687.50	11,213,381.44
6	Penulangan	7024.84	Kg	Analisa B.17.a	11,027.50	77,466,465.95
7	Lantai Kerja ( K100, $f_c = 7,4$ Mpa)	44	m3	Analisa SNI 7394 2008	633,710.00	27,883,240.00
8	Pengecoran Beton ( Ready Mix )	231	m3	Analisa Pengecoran Beton Ready Mix	1,372,365.50	317,016,430.50
<b><i>SUB TOTAL B</i></b>						<b>539,894,982.92</b>
<b><i>SUB TOTAL A + B</i></b>						<b>540,487,982.92</b>
<b><i>PPN 10%</i></b>						<b>54,048,798.29</b>
<b><i>JUMLAH</i></b>						<b>594,536,781.22</b>
<b><i>DIBULATKAN</i></b>						<b>594,536,000.00</b>
<b>LIMA RATUS SEMBILAN PULUH EMPAT JUTA LIMA RATUS TIGA PULUH ENAM RIBU RUPIAH</b>						