

## Lampiran 8

No	Pekerjaan	Volume	Satuan	Optimis	Pesimis	Most Likely
<b>I</b>						
<b>Lantai 1</b>						
A	Pondasi (150 150)	8,01	m'	7	10	7
1	Lantai kerja pondasi	2,01	m'	1	2	1
2	Pemasangan pondasi batu kali			2	4	2
B	Sloof (250 250)	10,01	m'			
1	Perapukan					
2	Lantai kerja					
3	Pembesian			2	5	3
4	Bekisting			3	5	4
5	Cor			1	3	1
C	Kolom (350 350)	6,06	m'			
1	Pembesian			3	5	4
2	Bekisting			4	7	6
3	Cor			1	2	1
D	Pelat Tangga	1,98	m'			
1	Pembesian			1	3	2
2	Bekisting			1	3	2
3	Cor			1	2	1
E	Pondasi Tangga	0,30	m'			
1	Pembesian			1	2	1
2	Bekisting			1	2	1
3	Cor			1	2	1
F	Balok Bordes (200 400)	0,48	m'			
1	Pembesian			2	3	2
2	Bekisting			2	4	2
3	Cor			1	1	1
<b>II</b>						
<b>Lantai 2</b>						
A	Kolom (350 350)	7,61	m'			
1	Pembesian			3	7	4
2	Bekisting			5	8	7
3	Cor			1	2	1
B	Balok Lantai (250 600)	13,40	m'			
1	Pembesian			5	9	7
2	Bekisting			6	9	7
3	Cor			1	2	1
C	Balok Atap (250 600)	6,42	m'			