

Lampiran 7. Biaya Cost Slope Setelah Percepatan Proyek

Pekerjaan	Satuan	Durasi Normal (Day)	Upah Total Pekerja Sebelum Percepatan (Rp)	Durasi Percepatan (Day)	Upah Total Pekerja Setelah Percepatan	Cost Slope/ Hari (Rp)
Pekerjaan Galian Biasa		18		12		
Tenaga						
Pekerja	OH		544.880		900.000	
Mandor	OH		354.172		650.000	
			16.182.936		18.600.000	402.844
Timbunan Biasa dari Selain Sumber Bahan		24		18		
Tenaga						
Pekerja	OH		6.186.658		9.300.000	
Mandor	OH		2.010.664		3.120.000	
			196.735.735		223.560.000	4.470.711
Timbunan Pilihan (Bouxit Batam)		24		18		
Tenaga						
Pekerja	OH		14.079.220		21.200.000	
Mandor	OH		9.153.372		13.780.000	
			557.582.186		629.640.000	12.009.636
Penyiapan badan Jalan		30		21		
Tenaga						
Pekerja	OH		170.660		300.000	
Mandor	OH		54.418		130.000	
			6.752.340		9.030.000	253.073
Total Keseluruhan Cost Slope Setelah Percepatan (Crashing)						17.136.264