

Lampiran 9. Perhitungan Produktivitas, Durasi *Crashing*, Upah *Shift*, Dan Total Pekerja

No.	Pekerjaan	Uraian	Sistem Shift	waktu	Upah (hari)	Cost	Total Cost/hari	Total Cost On Time	Upah Total Pekerja
1	Cor pilecape P1 uk. 1600x1600 mm $f_c = 25$ MPa	Beton cor K500	kap.kerja/hari	Crash Shift	REGULER	Shift malam	shift malam		
		Tukang Batu	7,400	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 119.750,11
		Kepala Tukang Batu	74,000	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 12.896,17
		Pekerja	1,233	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 663.231,39
		Mandor	23,125	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 44.215,43
		Besi Tulangan							
		Tukang besi	26,429	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 33.530,03
		kepala tukang besi	264,286	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 3.610,93
		Pekerja	26,429	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 30.950,80
		Mandor	462,500	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 2.210,77
		Bekisting							
		Tukang kayu	7,115	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 124.540,12
		Kepala Tukang Kayu	71,154	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 13.412,01
		Pekerja	3,558	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 229.920,22
		Mandor	71,154	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 14.370,01
		Srutwerk						Rp -	Rp -
		Tukang kayu						Rp -	Rp -
		Kepala Tukang Kayu						Rp -	Rp -
		Pekerja						Rp -	Rp -
		Mandor						Rp -	Rp -
		Pembongkaran cetakan						Rp -	Rp -
		Pekerja	30,833	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 26.529,26
		Mandor	308,333	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 3.316,16
				12,000				Rp 24.381.000,00	Rp 1.322.483,39

Lanjutan Lampiran 9. Perhitungan Produktivitas, Durasi *Crashing*, Upah *Shift*, Dan Total Pekerja

No.	Pekerjaan	Uraian	Sistem Shift	waktu	Upah (hari)	Cost	Total Cost/hari	Total Cost On Time	Upah Total Pekerja
2	Cor kolom K1 400 x 500 mm $f_c = 25$ MPa	Beton cor K500	kap.kerja/hari	Crash Shift	REGULER	shift malam	shift malam		
		Tukang Batu	7,400	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 594.137,14
		Kepala Tukang Batu	74,000	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 63.984,00
		Pekerja	1,233	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 3.290.605,71
		Mandor	23,125	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 219.373,71
		Besi Tukangan							
		Tukang besi	26,429	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 166.358,40
		kepala tukang besi	264,286	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 17.915,52
		Pekerja	26,429	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 153.561,60
		Mandor	462,500	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 10.968,69
		Bekisting							
		Tukang kayu	5,606	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 784.261,03
		Kepala Tukang Kayu	56,061	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 84.458,88
		Pekerja	2,803	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 1.447.866,51
		Mandor	56,061	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 90.491,66
		Sututwerk							
		Tukang kayu	2,803	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 1.568.522,06
		Kepala Tukang Kayu	5,606	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 844.588,80
		Pekerja	56,061	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 72.393,33
		Mandor	56,061	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 90.491,66
		Pembongkaran cetakan							
		Pekerja	30,833	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 131.624,23
		Mandor	308,333	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 16.453,03
				12,000				Rp 31.347.000,00	Rp 9.648.055,95

Lanjutan Lampiran 9. Perhitungan Produktivitas, Durasi *Crashing*, Upah *Shift*, Dan Total Pekerja

No.	Pekerjaan	Uraian	Sistem Shift	waktu	Upah (hari)	Cost	Total Cost/hari	Total Cost On Time	Upah Total Pekerja
3	Cor kolom K1 400 x 500 mm $f_c = 25$ MPa	Beton cor K500	kap.kerja/hari	Crash Shift	REGULER	shift malam	shift malam		
		Tukang Batu	7,400	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 511.085,71
		Kepala Tukang Batu	74,000	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 55.040,00
		Pekerja	1,233	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 2.830.628,57
		Mandor	23,125	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 188.708,57
		Besi Tukangan							
		Tukang besi	26,429	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 143.104,00
		kepala tukang besi	264,286	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 15.411,20
		Pekerja	26,429	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 132.096,00
		Mandor	462,500	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 9.435,43
		Bekisting							
		Tukang kayu	5,606	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 674.633,14
		Kepala Tukang Kayu	56,061	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 72.652,80
		Pekerja	2,803	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 1.245.476,57
		Mandor	56,061	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 77.842,29
		Sututwerk							
		Tukang kayu	2,803	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 1.349.266,29
		Kepala Tukang Kayu	5,606	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 726.528,00
		Pekerja	56,061	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 62.273,83
		Mandor	56,061	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 77.842,29
		Pembongkaran cetakan							
		Pekerja	30,833	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 113.225,14
		Mandor	308,333	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 14.153,14
				12,000				Rp 31.347.000,00	Rp 8.299.402,97

Lanjutan Lampiran 9. Perhitungan Produktivitas, Durasi *Crashing*, Upah *Shift*, Dan Total Pekerja

No.	Pekerjaan	Uraian	Sistem Shift	waktu	Upah (hari)	Cost	Total Cost/hari	Total Cost On Time	Upah Total Pekerja
4	Cor plat lantai A1 t: 140 mm f _c = 25 MPa	Beton cor K500	kap.kerja/hari	Crash Shift	REGULER	shift malam	shift malam		
		Tukang Batu	7,400	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 1.682.645,90
		Kepala Tukang Batu	74,000	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 181.208,02
		Pekerja	1,233	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 9.319.269,60
		Mandor	23,125	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 621.284,64
		Besi Tukangan							
		Tukang besi	26,429	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 471.140,85
		kepala tukang besi	264,286	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 50.738,25
		Pekerja	26,429	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 434.899,25
		Mandor	462,500	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 31.064,23
		Bekisting							
		Tukang kayu	5,606	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 2.221.092,59
		Kepala Tukang Kayu	56,061	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 239.194,59
		Pekerja	2,803	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 4.100.478,62
		Mandor	56,061	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 256.279,91
		Srutwerk							
		Tukang kayu	2,803	11,351	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.677.000,00	Rp 4.442.185,18
		Kepala Tukang Kayu	5,606	11,351	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.806.000,00	Rp 2.391.945,86
		Pekerja	56,061	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 205.023,93
		Mandor	56,061	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 256.279,91
		Pembongkaran cetakan							
		Pekerja	30,833	11,351	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.548.000,00	Rp 372.770,78
		Mandor	308,333	11,351	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.935.000,00	Rp 46.596,35
				12,000				Rp 31.347.000,00	Rp 27.324.098,47

Lanjutan Lampiran 9. Perhitungan Produktivitas, Durasi *Crashing*, Upah *Shift*, Dan Total Pekerja

No.	Pekerjaan	Uraian	Sistem Shift	waktu	Upah (hari)	Cost	Total Cost/hari	Total Cost On Time	Upah Total Pekerja
5	Cor kolom K1 400 x 500 mm $f_c = 25$ MPa	Beton cor K500	kap.kerja/hari	Crash Shift	REGULER	shift malam	shift malam		
		Tukang Batu	7,400	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 191.657,14
		Kepala Tukang Batu	74,000	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 20.640,00
		Pekerja	1,233	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 1.061.485,71
		Mandor	23,125	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 70.765,71
		Besi Tukangan							
		Tukang besi	26,429	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 53.664,00
		kepala tukang besi	264,286	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 5.779,20
		Pekerja	26,429	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 49.536,00
		Mandor	462,500	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 3.538,29
		Bekisting							
		Tukang kayu	5,606	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 252.987,43
		Kepala Tukang Kayu	56,061	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 27.244,80
		Pekerja	2,803	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 467.053,71
		Mandor	56,061	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 29.190,86
		Srutwerk							
		Tukang kayu	2,803	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 505.974,86
		Kepala Tukang Kayu	5,606	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 272.448,00
		Pekerja	56,061	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 23.352,69
		Mandor	56,061	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 29.190,86
		Pembongkaran cetakan							
		Pekerja	30,833	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 42.459,43
		Mandor	308,333	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 5.307,43
				8,000				Rp 20.898.000,00	Rp 3.112.276,11

Lanjutan Lampiran 9. Perhitungan Produktivitas, Durasi *Crashing*, Upah *Shift*, Dan Total Pekerja

No.	Pekerjaan	Uraian	Sistem Shift	waktu	Upah (hari)	Cost	Total Cost/hari	Total Cost On Time	Upah Total Pekerja
6	Cor kolom K2 400 x 400 mm $f_c = 25$ MPa	Beton cor K500	kap.kerja/hari	Crash Shift	REGULER	shift malam	shift malam		
		Tukang Batu	7,400	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 19.165,71
		Kepala Tukang Batu	74,000	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 2.064,00
		Pekerja	1,233	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 106.148,57
		Mandor	23,125	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 7.076,57
		Besi Tukangan							
		Tukang besi	26,429	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 5.366,40
		kepala tukang besi	264,286	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 577,92
		Pekerja	26,429	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 4.953,60
		Mandor	462,500	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 353,83
		Bekisting							
		Tukang kayu	5,606	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 25.298,74
		Kepala Tukang Kayu	56,061	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 2.724,48
		Pekerja	2,803	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 46.705,37
		Mandor	56,061	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 2.919,09
		Srutwerk							
		Tukang kayu	2,803	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 50.597,49
		Kepala Tukang Kayu	5,606	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 27.244,80
		Pekerja	56,061	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 2.335,27
		Mandor	56,061	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 2.919,09
		Pembongkaran cetakan							
		Pekerja	30,833	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 4.245,94
		Mandor	308,333	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 530,74
				8,000				Rp 20.898.000,00	Rp 311.227,61

Lanjutan Lampiran 9. Perhitungan Produktivitas, Durasi *Crashing*, Upah *Shift*, Dan Total Pekerja

No.	Pekerjaan	Uraian	Sistem Shift	waktu	Upah (hari)	Cost	Total Cost/hari	Total Cost On Time	Upah Total Pekerja
7	Cor kolom K4 250 x 250 mm $f_c = 25$ MPa	Beton cor K500	kap.kerja/hari	Crash Shift	REGULER	shift malam	shift malam		
		Tukang Batu	7,400	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 67.379,46
		Kepala Tukang Batu	74,000	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 7.256,25
		Pekerja	1,233	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 373.178,57
		Mandor	23,125	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 24.878,57
		Besi Tukangan							
		Tukang besi	26,429	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 18.866,25
		kepala tukang besi	264,286	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 2.031,75
		Pekerja	26,429	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 17.415,00
		Mandor	462,500	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 1.243,93
		Bekisting							
		Tukang kayu	5,606	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 88.940,89
		Kepala Tukang Kayu	56,061	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 9.578,25
		Pekerja	2,803	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 164.198,57
		Mandor	56,061	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 10.262,41
		Srutwerk							
		Tukang kayu	2,803	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 177.881,79
		Kepala Tukang Kayu	5,606	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 95.782,50
		Pekerja	56,061	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 8.209,93
		Mandor	56,061	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 10.262,41
		Pembongkaran cetakan							
		Pekerja	30,833	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 14.927,14
		Mandor	308,333	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 1.865,89
				8,000				Rp 20.898.000,00	Rp 1.092.293,68

Lanjutan Lampiran 9. Perhitungan Produktivitas, Durasi *Crashing*, Upah *Shift*, Dan Total Pekerja

No.	Pekerjaan	Uraian	Sistem Shift	waktu	Upah (hari)	Cost	Total Cost/hari	Total Cost On Time	Upah Total Pekerja
8	Cor balok B1 400 x 600 $f_c = 25$ MPa	Beton cor K500	kap.kerja/hari	Crash Shift	REGULER	shift malam	shift malam		
		Tukang Batu	7,400	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 258.353,83
		Kepala Tukang Batu	74,000	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 27.822,72
		Pekerja	1,233	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 1.430.882,74
		Mandor	23,125	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 95.392,18
		Besi Tukangan							
		Tukang besi	26,429	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 72.339,07
		kepala tukang besi	264,286	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 7.790,36
		Pekerja	26,429	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 66.774,53
		Mandor	462,500	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 4.769,61
		Bekisting							
		Tukang kayu	5,606	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 341.027,05
		Kepala Tukang Kayu	56,061	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 36.725,99
		Pekerja	2,803	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 629.588,41
		Mandor	56,061	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 39.349,28
		Srutwerk							
		Tukang kayu	2,803	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 682.054,11
		Kepala Tukang Kayu	5,606	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 367.259,90
		Pekerja	56,061	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 31.479,42
		Mandor	56,061	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 39.349,28
		Pembongkaran cetakan							
		Pekerja	30,833	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 57.235,31
		Mandor	308,333	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 7.154,41
				8,000				Rp 20.898.000,00	Rp 4.195.348,20

Lanjutan Lampiran 9. Perhitungan Produktivitas, Durasi *Crashing*, Upah *Shift*, Dan Total Pekerja

No.	Pekerjaan	Uraian	Sistem Shift	waktu	Upah (hari)	Cost	Total Cost/hari	Total Cost On Time	Upah Total Pekerja
9	Cor plat lantai A2 t: 140 mm $f_c = 25$ MPa	Beton cor K500	kap.kerja/hari	Crash Shift	REGULER	shift malam	shift malam		
		Tukang Batu	7,400	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 929.533,15
		Kepala Tukang Batu	74,000	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 100.103,57
		Pekerja	1,233	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 5.148.183,60
		Mandor	23,125	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 343.212,24
		Besi Tukangan							
		Tukang besi	26,429	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 260.269,28
		kepala tukang besi	264,286	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 28.029,00
		Pekerja	26,429	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 240.248,57
		Mandor	462,500	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 17.160,61
		Bekisting							
		Tukang kayu	5,606	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 1.226.983,76
		Kepala Tukang Kayu	56,061	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 132.136,71
		Pekerja	2,803	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 2.265.200,78
		Mandor	56,061	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 141.575,05
		Srutwerk							
		Tukang kayu	2,803	7,568	Rp 65.000,00	Rp 74.750,00	Rp 139.750,00	Rp 1.118.000,00	Rp 2.453.967,52
		Kepala Tukang Kayu	5,606	7,568	Rp 70.000,00	Rp 80.500,00	Rp 150.500,00	Rp 1.204.000,00	Rp 1.321.367,12
		Pekerja	56,061	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 113.260,04
		Mandor	56,061	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 141.575,05
		Pembongkaran cetakan							
		Pekerja	30,833	7,568	Rp 60.000,00	Rp 69.000,00	Rp 129.000,00	Rp 1.032.000,00	Rp 205.927,34
		Mandor	308,333	7,568	Rp 75.000,00	Rp 86.250,00	Rp 161.250,00	Rp 1.290.000,00	Rp 25.740,92
				8,000				Rp 20.898.000,00	Rp 15.094.474,32